



Philippine Economic Zone Authority

Bids and Awards Committee
BID BULLETIN NO. s.2018 - 02
07 November 2018


“Rehabilitation of CEZ Gates and Main Guard Houses at Gates 1 to 5 and Construction of New Guard House at Gate 6”
Reference No. PEZA-CEZ 18-10-010

This Bid Bulletin is issued to modify or amend the following provisions in the Bidding Documents, as a result of the Pre-Bid Conference held on November 6, 2018 for the Project “*Rehabilitation of CEZ Gates and Main Guard Houses at Gates 1 to 5 and Construction of New Guard House at Gate 6*”. This shall form an integral part of the Bid Documents.

See attached Revised Format for:

1. Bid Price Schedule - (Annex A)
2. Scope of Work - (Annex B)

Please be guided accordingly.


LEVI D. VIZMANOS
Chairperson, CEZ - BAC

SCOPE OF WORKS (REVISED)

PROJECT : Rehabilitation of CEZ Main Guard Houses and Gates at Gate 1 to 5 and Construction of New Guard House at Gate 6

LOCATION : Cavite Economic Zone, Rosario Cavite

DATE : November 07, 2018

The work to be performed for the project consist of furnishing of all materials, labor, tools, and other incidentals to complete the project in accordance with the plans and works enumerated hereunder.

GUARD HOUSE 1

- Dismantling of roof, ceiling, vinyl tiles, windows and plumbing fixtures (water closet & lavatory) and windows.
- Installation of new roof and storm drain.
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Replace all existing lightings from fluorescent to pin lights.
- Replace all windows to analok sliding glass windows.
- Replace all existing doors.

GUARD HOUSE 2

- Dismantling of ceiling, vinyl tiles, windows and plumbing fixtures (water closet & lavatory)
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Extension of existing toilet
- Replace all existing lightings from fluorescent to pin lights.
- Replace all windows to analok sliding glass windows.
- Replace all existing doors.
- Repainting of roof.

GUARD HOUSE 3

- Dismantling of ceiling, vinyl tiles, windows and plumbing fixtures (water closet & lavatory)
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.

- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Replace all existing lightings from fluorescent to pin lights.
- Replace all windows to analog sliding glass windows.
- Replace all existing doors.
- Repainting of roof.

CORAL OFFICE AT GATE 3 (BOC OFFICE)

- Dismantling of ceiling and plumbing fixtures (water closet & lavatory)
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Replace all existing lightings from fluorescent to pin lights.
- Painting of roof.
- Repainting of roof framing outside office.

GUARD HOUSE 4

- Dismantling of ceiling, vinyl tiles, windows and plumbing fixtures (water closet & lavatory)
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Extension of existing toilet
- Replace all existing lightings from fluorescent to pin lights.
- Replace all windows to analog sliding glass windows.
- Replace all existing doors.
- Repainting of roof.
- Installation of additional chamber of existing septic tank.

GUARD HOUSE 5

- Dismantling of ceiling, windows and plumbing fixtures (water closet & lavatory)
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new water closet and lavatory. (Replace existing)
- Replace all existing lightings from fluorescent to pin lights.
- Replace all windows to analog sliding glass windows.
- Replace all existing doors.
- Repainting of roof.

GUARD HOUSE 6

- CHB Enclosure and plastering of wall.
- Installation of new ceiling.
- Installation of new floor tiles and new wall & floor tiles at toilet.
- Painting of wall (interior & exterior) and ceiling.
- Installation of new sanitary line, water line and plumbing fixtures.
- Installation of new electrical line and lightings.
- Installation of new analog sliding glass windows.
- Installation of new doors.

GATES 1 TO 6

- Repainting of guard posts of gates 1 & 3
- Replacement of damaged rails at gates 1 & 3
- Lubrication of all gates' wheels and hinges
- Replacement of gate's wheels at gate 3
- Repainting of steel gates

Prepared by:
(sgd)

Engr. Crislyn C. Andalis
Civil Engineer – ESO III

Checked by:
(sgd)

Engr. Jose A. Ibasco
Civil Engineer – ENGR. III

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
I.	GENERAL REQUIREMENTS							
	Mobilization / Demobilization		1.00	lot				
	VAT		1.00	lot				
II.	CONSTRUCTION SAFETY AND HEALTH PROGRAM							
	MATERIALS							
	Working Gloves (Free Size)		24.00	pcs.				
	Face Mask		24.00	pcs.				
	Welding Mask		2.00	pcs.				
	EQUIPMENT RENTALS							
	N/A							
	LABOR							
	1-Safety Officer		240.00	hrs.				
	VAT		1.00	lot				
III.	DISMANTLING WORKS GUARD HOUSE 1 TO 5							
	(ceiling, vinyl tiles, plumbing fixtures, windows of GH 1 to 5 ; roof of GH 1)							
	MATERIALS							
	N/A							
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	H-Frame		1.00	lot				
	LABOR							
	1-Foreman		120.00	hrs.				
	4-Skilled Laborer		120.00	hrs.				
	4-Unskilled Laborer		120.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	VAT		1.00	lot				
IV.	INSTALLATION OF NEW ROOF & STORM DRAIN @ GH 1							
	MATERIALS							
	Pre-painted long span rib type 8' Ga. 24 (24 sheets)		58.52	lm				
	Ridge roll 24"x8"x0.6mm		5.00	pcs				
	Box type outside gutter 48"x8"x0.6mm		8.00	pcs				
	Tekscrews 12x55		720.00	pcs				
	1.5mm C-Purlins 2"x3" @ 6m length		12.00	pcs				
	Blind Rivet		2.00	box				
	Welding Rod		20.00	kls				
	Angle bar 2"x2"x1/4		12.00	pcs				
	Epoxy Primer		2.00	gal				
	Sagrod 12mm dia. Round bar x 6m		5.00	pcs				
	PVC Pipe 100mm S-600		7.00	pcs				
	PVC Elbow equal 100mm		12.00	pcs				
	Neltex Pipe Cement		2.00	can				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	1-Welding Machine		27.00	hrs.				
	LABOR							
	1-Foreman		46.00	hrs.				
	3-Skilled Laborer		46.00	hrs.				
	3-Unskilled Laborer		46.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
V.	INSTALLATION OF NEW CEILING AT GH 1 TO 6 AND BOC OFFICE AT GATE 3							
	MATERIALS							
	Hardiflex 1/4		58.00	pcs				
	Wall Angle		60.00	pcs				
	C-Channel Clip		29.00	pcs				
	Metal Furring		45.00	pcs				
	Blind Rivets		7.00	box				
	Black Screws		1,740.00	pcs				
	Threaded Rod 10mm		35.00	pcs				
	Nut & Washer 10mm		500.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		107.00	hrs.				
	2-Skilled Laborer		107.00	hrs.				
	2-Unskilled Laborer		107.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
VI.	INSTALLATION OF NEW FLOOR/WALL TILES AT GH 1 TO 6 AND BOC OFFICE AT GATE 3							
	MATERIALS							
	Ceramic Floor and Wall Tiles 300mmx300mm		1,879.00	pcs				
	Tile Adhesive		40.00	bags				
	Tile Grout		30.00	bags				
	Tile Trim		28.00	pcs				
	EQUIPMENT / TOOLS RENTALS							

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		137.00	hrs.				
	2-Skilled Laborer		137.00	hrs.				
	2-Unskilled Laborer		137.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
VII.	CHB ENCLOSURE & PLASTERING OF WALL AT GATE 6							
	MATERIALS							
	Cement		45.00	bags				
	Sand		4.00	cu.m.				
	CHB 4"		400.00	pcs				
	RSB 12mm		8.00	pcs				
	RSB 10mm		11.00	pcs				
	Tie Wire #16		0.70	kgs				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		22.00	hrs.				
	3-Skilled Laborer		22.00	hrs.				
	3-Unskilled Laborer		22.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
VIII.	PAINTING OF CEILING, WALL & DOORS at GH 1 to 6 & BOC OFFICE AT GATE 3							

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	MATERIALS							
	Boysen, Flat latex (white)		20.00	gal				
	Boysen, Semi-gloss Latex		60.00	gal				
	Patching Compound		5.00	bags				
	Sanding paper		80.00	pcs				
	Fiber Mesh tape		5.00	rolls				
	Paint Brush 2"		17.00	pcs				
	Paint Roller 6"		18.00	pcs				
	Lacquer Thinner		20.00	gals				
	Boysen, Quick Dry Enamel		13.00	gal				
	Acrylic Paint (tinting colors)		60.00	can				
	Boysen, Flat Wall Enamel		1.00	gal				
	Round Rugs		10.00	kg				
	EQUIPMENT / TOOLS RENTALS							
	N/A							
	LABOR							
	1-Foreman		122.00	hrs.				
	2-Skilled Laborer		122.00	hrs.				
	2-Unskilled Laborer		122.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
IX.	INSTALLATION OF PLUMBING FIXTURES AT GH 1 TO 6 AND BOC OFFICE AT GATE 3							
	MATERIALS							
	Water Closet		set	7.00				
	Bidet		pc	7.00				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 & 5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	Angle Valve		pc	6.00				
	Flexible hose		pc	6.00				
	Lavatory		set	7.00				
	P-Trap (Stainless)		pc	5.00				
	PPR Pipe 20mm		pc	10.00				
	PPR Connectors		lot	1.00				
	Goose Neck faucet		pc	7.00				
	Neltex pipe cement		can	5.00				
	Teflon Tape		pc	5.00				
	Stainless Steel Floor drain		pc	5.00				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		56.00	hrs.				
	2-Skilled Laborer		56.00	hrs.				
	2-Unskilled Laborer		56.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
X.	EXTENSION OF TOILET AT GH 2 & 4							
	MATERIALS							
	Cement		9.00	bags				
	Sand		1.00	cu.m.				
	CHB 4"		100.00	pcs				
	RSB 10mm		8.00	pcs				
	Tie Wire		1.00	kgs				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		9.00	hrs.				
	2-Skilled Laborer		9.00	hrs.				
	2-Unskilled Laborer		9.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XI.	REPLACEMENT OF ELECTRICAL DEVICES AT GH 1 TO 5 AND BOC OFFICE AT GATE 3							
	MATERIALS							
	LED Pinlight 9Watts		40.00	set				
	THHN Wire 3.5mm		3.00	box				
	Flexible hose 1/2		1.50	roll				
	Electrical tape (big)		10.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		41.00	hrs.				
	2-Skilled Laborer		41.00	hrs.				
	2-Unskilled Laborer		41.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XII.	INSTALLATION OF NEW WINDOWS (SUPPLY & INSTALL)							
	MATERIALS / LABOR							

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	<i>Analok sliding glass window</i>							
	GH1 - 1.85m x 1.03m (2 Division)		1.00	set/s				
	GH1 - 3.06m x 1.03m (3 Division)		1.00	set/s				
	GH1 - 1.80m x 1.03m (2 Division)		2.00	set/s				
	GH1 - 2.10m x 1.03m (3 Division)		1.00	set/s				
	GH2 - 1.48m x 0.87m (2 Division)		2.00	set/s				
	GH2 - 1.97m x 0.87m (2 Division)		1.00	set/s				
	GH3 - 1.40m x 1.17m (2 Division)		2.00	set/s				
	GH3 - 1.40m x 1.08m (2 Division)		1.00	set/s				
	GH3 - 2.07m x 1.17m (2 Division)		1.00	set/s				
	GH4 - 2.45m x 0.95m (4 Division)		1.00	set/s				
	GH4 - 1.00m x 1.00m (1 Division)		1.00	set/s				
	GH5 - 1.10m x 1.00m (2 Division)		1.00	set/s				
	GH6 - 1.80m x 1.20m (2 Division)		2.00	sets				
	<i>Analok awning glass window</i>							
	0.40m x 0.40m		3.00	set/s				
	0.45m x 0.60m		2.00	set/s				
	0.40m x 0.80m		1.00	set/s				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XIII.	INSTALLATION OF NEW DOORS AT GH 1 TO 6 AND CORAL OFFICE							
	(Glass door not included)							
	MATERIALS							
	Door & Jamb, Panel 700-900x2100mm		12.00	set/s				
	Door & Jamb, PVC 600-800x2100mm		6.00	set/s				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	Hinges, Loose Pin 3"x3"		54.00	pc/s				
	Door Lockset		18.00	set/s				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		65.00	hrs.				
	2-Skilled Laborer		65.00	hrs.				
	2-Unskilled Laborer		65.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XIV.	REPAINTING OF ROOFS AT GH 2 TO 5 AND BOC OFFICE AT GATE 3							
	MATERIALS							
	Roof Paint (Beige)		8.00	gal				
	Lacquer Thinner		1.00	gal				
	Paint Roller 6"		2.00	pc				
	Paint Brush 2"		2.00	pc				
	EQUIPMENT / TOOLS RENTALS							
	N/A							
	LABOR							
	1-Foreman		17.00	hrs.				
	3-Skilled Laborer		17.00	hrs.				
	3-Unskilled Laborer		17.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
XV.	INSTALLATION OF NEW SANITARY LINE AT GH 6							
	MATERIALS							
	PVC pipe 100mm S-1000		4.00	pcs				
	PVC pipe 50mm S-1000		2.00	pcs				
	P-trap 50mm		1.00	pc				
	Floor Drain		1.00	pc				
	PVC elbow 100x90		4.00	pcs				
	PVC elbow 100x45		2.00	pcs				
	PVC wye reducer 100x50		1.00	pc				
	PVC wye equal 50mm		1.00	pc				
	PVC wye equal 100mm		1.00	pc				
	PVC Tee 50mm		2.00	pcs				
	Neltex Pipe Cement 400cc		1.00	can				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		8.00	hrs.				
	1-Skilled Laborer		8.00	hrs.				
	1-Unskilled Laborer		8.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XVI.	INSTALLATION OF NEW WATER LINE AT GH 6							
	MATERIALS							
	PPR Pipe 20mm PN 20		3.00	pcs				
	PPR Elbow Equal 20mm		1.00	pcs				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	PPR Tee Equal 20mm		1.00	pcs				
	PPR Bushing Reducer 25x20		1.00	pc				
	PPR Gate Valve 20mm		1.00	pc				
	PPR Female threaded tee 20mm		1.00	pcs				
	PPR End Cap 20mm		1.00	pcs				
	PPR Female threaded adaptor 20mm x 1/2		1.00	pcs				
	Neltex Pipe Cement 400cc		1.00	can				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		10.00	hrs.				
	1-Skilled Laborer		10.00	hrs.				
	1-Unskilled Laborer		10.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XVII.	RESTORATION OF DAMAGED PAVEMENT AT GH 6							
	MATERIALS							
	Cement		3.00	bags				
	Sand		0.20	cu.m.				
	Gravel		0.30	cu.m.				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		2.00	hrs.				
	1-Skilled Laborer		2.00	hrs.				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	1-Unskilled Laborer		2.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XVIII.	INSTALLATION OF ADDT'L CHAMBER OF SEPTIC TANK AT GATE 4							
	MATERIALS							
	CHB 4"		165.00	pc/s				
	Cement		15.00	bag/s				
	Sand		1.00	cu.m.				
	Gravel		0.50	cu.m.				
	RSB 10mm dia.		15.00	pc/s				
	Tie Wire #16		1.00	kgs				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		26.00	hrs.				
	2-Skilled Laborer		26.00	hrs.				
	2-Unskilled Laborer		26.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XIX.	INSTALLATION OF ELECTRICAL LINE & LIGHTINGS AT GH 6							
	MATERIALS							
	Circuit Breaker Bolt-on 20AT		1.00	set				
	LED Pinlight 9Watts		1.00	set				
	LED Flourescent light 12Watts		2.00	set				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	THHN Wire 3.5mm		0.50	box				
	Wall Fan		1.00	set				
	EMT pipe 1/2		6.00	pcs				
	Junction box #16		3.00	pcs				
	Utility box #16		4.00	pcs				
	Electrical tape (big)		3.00	pcs				
	EMT connectors		1.00	lot				
	1-gang Switch		1.00	pcs				
	2-gang Switch		1.00	pcs				
	3-gang Outlet		2.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	LABOR							
	1-Foreman		17.00	hrs.				
	2-Skilled Laborer		17.00	hrs.				
	2-Unskilled Laborer		17.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XX.	REPAINTING OF ROOF FRAMING AT BOC OFFICE AT GATE 3							
	MATERIALS							
	Rust Converter		2.00	gal				
	Boysen, QDE		3.00	gal				
	Paint Brush 1"		2.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	N/A							

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	LABOR							
	1-Foreman		8.00	hrs.				
	2-Skilled Laborer		8.00	hrs.				
	2-Unskilled Laborer		8.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XXI.	REPAINTING OF GUARD POST AT GATES 1 & 3							
	MATERIALS							
	Boysen, Semi-gloss Latex (White)		2.00	gal				
	Acrycolor		2.00	can				
	Paint Roller 6"		1.00	pcs				
	Paint Brush 2"		1.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	N/A							
	LABOR							
	1-Foreman		4.00	hrs.				
	2-Skilled Laborer		4.00	hrs.				
	2-Unskilled Laborer		4.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XXII.	REPLACEMENT OF RAILS AT GATES 1 & 3							
	MATERIALS							
	Cement		5.00	bags				
	Sand		1.00	cu.m.				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
LOCATION : Cavite Economic Zone
SUBJECT : Price Schedule and Bid Quantities Form
DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	Welding Rods		30.00	kgs				
	Angle Bar 2"x2"x 1/4 x 20'		96.00	pcs				
	EQUIPMENT / TOOLS RENTALS							
	1-Welding Machine		38.00	hrs.				
	LABOR							
	1-Foreman		38.00	hrs.				
	3-Skilled Laborer		38.00	hrs.				
	3-Unskilled Laborer		38.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XXIII.	GATE WHEELS AND HINGES LUBRICATION AT GATES 1 TO 5 & REPLACEMENT OF GATE WHEELS AT GATE 3							
	MATERIALS							
	Gate Wheel Roller Caster 2" x 4"		28.00	set				
	WD40 (big)		5.00	btls				
	EQUIPMENT / TOOLS RENTALS							
	Minor Tools (e.g. hand tools)		1.00	lot				
	1-Welding Machine		56.00	hrs.				
	LABOR							
	1-Foreman		56.00	hrs.				
	3-Skilled Laborer		56.00	hrs.				
	3-Unskilled Laborer		56.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XXIX.	REPAINTING OF STEEL GATE 1 TO 6							

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	MATERIALS							
	Boysen, QDE		10.00	gal				
	Semi-gloss Latex		25.00	gal				
	Acry-color		25.00	can				
	Paint Roller 6"		4.00	pcs				
	Paint Brush 2"		4.00	pcs				
	Lacquer Thinner		2.00	gals				
	EQUIPMENT / TOOLS RENTALS							
	N/A							
	LABOR							
	1-Foreman		90.00	hrs.				
	2-Skilled Laborer		90.00	hrs.				
	2-Unskilled Laborer		90.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
XXX.	REPAIR OF GATES 1 TO 6 DAMAGED AREAS							
	MATERIALS							
	2mm, 2"x4"x20' Tubular		12.00	pcs				
	2mm, 1"x1"x20' Tubular		10.00	pcs				
	2mm, 1"x2"x20' Tubular		15.00	pcs				
	2mm, 2"x2"x20' Tubular		20.00	pcs				
	Welding Rod		20.00	kls				
	Other Consumables		1.00	lot				
	EQUIPMENT / TOOLS RENTALS							
	1-Welding Machine		32.00	hrs.				

PROJECT : REHABILITATION OF CEZ MAIN GUARD HOUSE AND GATES AT GATE 1,2,3,4 &5 AND CONSTRUCTION OF NEW GUARD HOUSE AT GATE 6
 LOCATION : Cavite Economic Zone
 SUBJECT : Price Schedule and Bid Quantities Form
 DATE : Revised - November 7, 2018

NO.	MATERIALS	DESCRIPTION	QTY.	UNIT	UNIT COST		TOTAL	
					FIGURE	In Words	FIGURE	In Words
	Acetylene / Oxygen		1.00	lot				
	LABOR							
	1-Foreman		32.00	hrs.				
	3-Skilled Laborer		32.00	hrs.				
	3-Unskilled Laborer		32.00	hrs.				
	OVERHEAD / CONTINGENCIES / MISC.		1.00	lot				
	PROFIT		1.00	lot				
	VAT		1.00	lot				
TOTAL PROJECT COST								

- Note:
- 1 Above quantities are approximate requirements of the contract, and serve only as basis for comparing bids, for progress payments, and for authorized changes in the contract.
 - 2 The Bid Prices entered for the different items are understood to be for the finished works complete in every aspect. The unit and total bid prices include direct and indirect expenses and all incidental and contingent cost, profit, overheads, allowances taxes, duties insurance, etc.
 - 3 The undersigned Bidder hereby certify that he has fully informed himself of all conditions, local or otherwise, affecting the carrying out of the Contract Work and that his proposal has been prepared in strict accordance with the terms and conditions of the Contract Documents.

 Bidders Signature