## PROJECT : PROPOSED CONSTRUCTION/IMPROVEMENT OF MEZ TEMPORARY OFFICE AT AA

LOCATION : MACTAN ECONOMIC ZONE, LAPU-LAPU CITY

Date : FEBRUARY 2020

DETAILED COST I		T ESTIMATES	
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
Ι.	GENERAL REQUIREMENTS		
	Mobilization/Demob	1.00	LOT
	Permit application, Structural investigation/analysis	1.00	lot
П.	EXCAVATION WORKS		
	Excavation	82.30	cu.m
А	Materials		
В	Equipment Rental @ 8 hrs/day		
C	Labor		
D	Estimated Direct Cost(EDC)=A+B+C		
E	Indirect Cost/Mark-Up		
	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
	Profit @ 8% of EDC		
	Sub-Total		
F	5% Value Added Tax of D + E		
G	Total Cost = D + E + F		
Н	Unit Cost		
III	CONCRETE WORKS	22.67	cu.m
	Materials		
	Portland Cement	225.00	bags
	3/4 Crushed Gravel	28.00	cu.m
	Washed Sand	15.00	cu.m
	20mm dia. Deformed Bars	60.00	pcs
	16mm dia. Deformed Bars	179.00	pcs
	10mm dia. Deformed Bars	263.00	pcs
	20mm dia. X 600mm Anchor Bolts	90.00	pcs
	16mm thk Steel Plate 4x8 ft.	2.00	sheets
	Tie Wires	2.00	rolls
	Formworks and Hardwares	1.00	lot
В	Equipment Rental @ 8 hrs/day	1	
	Cocrete Mixer	15.00	days
			,
C	Labor		
C	Labor Foreman	37.00	days
C		37.00 74.00	days days

	Laborer/Helper (DOLE's minimum wage for region 7)	111.00	days
		111.00	uuys
	Estimated Direct Cost(EDC)=A+B+C		
	Indirect Cost/Mark-Up		
E	· · · · ·		
	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
	Profit @ 8% of EDC		
	Sub-Total		
	5% Value Added Tax of D + E		
	Total Cost = D + E + F		
H	Unit Cost		
	STEEL WORKS (COLUMN, BEAMS, MEZZANINE FLOOR		
IV	AND FLOOR FRAMING	1.00	lot
	Columns, Beams, Floor joist frame, floor joist, steel stais,		
	aircon/condenser flatform		
A	Materials		
	W14x53 x 6.0m Flange (I-Beam)	9.00	lengths
	W12 x 40 x 6.0m Flange (I-Beam)	34.00	lengths
	2x6 C- Channel x 6.0mm Thk. w/10mm steel bars bracing	36.00	lengths
	1.5mm thk. 2 x 3 x 6.0m C-Purlins	284.00	pcs
	1" Thk. Marine Plywood	110.00	sheets
	1/4 x 2 x 2 Angle Bars	4.00	pcs
	1/4 x 1 1/2 Angle Bars	23.00	pcs
	3/16 x 1 Angle Bars	35.00	pcs
	3/16 x 1 1/2 Flat Bar	15.00	pcs
	Stainless Stair Railings and Handrail	1.00	lot
	Painting works	1.00	lot
	Welding Rods and Hardwares	1.00	lot
D	Equipment Rental @ 8 hrs/day		
D	Portable Lifter	1.00	lot
	Welding Machine w/ Generator	32.00	
		52.00	days
~	Labor		
Ľ		22.00	dava
	Leadman/Foreman	32.00	days
	Welder	248.00	days
	Carpenter	64.00	days
	Laborer/Helper (DOLE's minimum wage for region 7)	160.00	days
	Estimated Direct Cost(EDC)=A+B+C		
E	Indirect Cost/Mark-Up		
	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
	Profit @ 8% of EDC		
	Sub-Total		
F	5% Value Added Tax of D + E		

G	Total Cost = D + E + F		
Н	Unit Cost		
V	FLOOR, WALL AND CEILING FINISHES		
A	Materials		
	Floor Finishes:		
	600x600mm Ceramic/China Granite Tiles w/ complete		
	accessories and floor preparation(ZA/DG's Office)	92.94	sq.m
	300 x 300mm Ceramic Floor Tiles w/ complete accessories and		
	floor preparation(DG/ZA, OZA CR	16.80	sq.m
	300 x300mm Vinyl Floor Tiles w/ complete accessories and	10.00	34
	floor preparation(Other area)	416.00	sq.m
		110.00	59.111
	Wall Finishes:		
	Drywall (double wall) partition, 6mm hardiflex board on 1.5 x 3		
	metal studs frame w/ paint finish	504.64	sa m
	Drywall (double wall) partition, 6mm hardiflex board on	504.04	sq.m
	1.5mm x 2 x 4 C-Purlins frame w/ paint finish	101 00	ca m
	1.311111 X Z X 4 C-FULINIS ITALILE W/ PAUL IIIIISI	121.20	sq.m
	Coromic well tiles (CD) w/ complete correction (DC/074-CD)	C2 20	
	Ceramic wall tiles (CR) w/ complete accessories (DG/OZA CR)	63.20	sq.m
	4" CHB wall partion CR (DG/ZA Office)	9.20	sq.m
	Ceiling Finishes:		
	2/4 ft. Boral/Acoustic Ceiling Board on powder coated T-		
	runner, cross tee and wall angle frame	1,257.77	sq.m
	4mm thk. Hardiflex board on metal furring frame w/ paint		
	finish	197.00	sq.m
В	Equipment Rental @ 8 hrs/day		
C	Labor	1.00	lot
D	Estimated Direct Cost(EDC)=A+B+C		
	Indirect Cost/Mark-Up		
	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
	Profit @ 8% of EDC		
	Sub-Total		
г	5% Value Added Tax of D + E		
	Total Cost = D + E + F		
H	Unit Cost		
VI	DOORS, WINDOWS AND PLUMBING WORKS		
A	Materials		
	2.0 X 2.10 Double Swing Door 3/8 glass on analok aluminum		
	frame w/ complete accessories	2.00	sets
	1.60 X 2.10 Double Swing Door 3/8 glass on analok aluminum		
	frame w/ complete accessories	6.00	sets
	0.80 x 2.10 Flush Door on 2 x 4 Treated Door Jamb	27.00	sets

	0.70 x 2.10 Flush Door on 2 x 4 Treated Door Jamb	10.00	sets
	1.2 x 1.5 Fixed Glass Counter w/ Hole 3/8 Glass (EAD)	4.00	sets
	1.2 x 1.8 Fixed Glass Counter w/ Hole 3/8 Glass (Cashier)	1.00	sets
	Water Closet, Lavatory, soap and tissue holder (DG's office)	1.00	set
В	Equipment Rental @ 8 hrs/day		
C	Labor		
	Foreman/Leadman	20.00	days
	Mason Carpenter	40.00	days
	Laborer/Helper (DOLE's minimum wage for region 7)	40.00	days
	Estimated Direct Cost(EDC)=A+B+C		
	Indirect Cost/Mark-Up		
E			
	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
	Profit @ 8% of EDC		
	Sub-Total		
	5% Value Added Tax of D + E		
	Total Cost = D + E + F		
Н	Unit Cost		
VII	ELECTRICAL WORKS		
	Materials		
1	Transformer		
	Transformer (167 kva)	3	unit
	Pole mounted type		
1.1	oil immersed, 13.2/230volt		
1.2	Transformer's (accessories)	1	lot
1.3	Concrete Pole (40 ft)	1	unit
	Pole accessories	1	lot
2	Automatic Transfer switch		
2.1	ATS w/ accessories	1	unit
	KWHR Meter	1	unit
3	Wire/Cables		
4	Wires/Cable: 200 mm.sq		
5	Wires/Cable: 100 mm.sq	300	mtr
6	Wires/Cable: 80 mm.sq	445	mtr
7	Wires/Cable: 60 mm.sq	150	mtr
8	Wires/Cable: 38 mm.sq	200	mtr
9	Wires/Cable: 30 mm.sq	150	mtr
10	Wires/Cable: 8.0 mm.sq	8	box
11	Wires/Cable: 5.5 mm.sq	14	box
	Wires/Cable: 3.5 mm.sq	18	box
12	Circuit Breaker		
	MDP-1000 A, 3PHASE	1	unit

14	CB-250 A	8	unit
14	CB-150 A	4	unit
15	CB-125 A	2	unit
15	CB-100 A	2	unit
16	CB-75 A	2	unit
17	CB-60 A	2	unit
18	CB-50 A	2	unit
19	CB-30 A	76	unit
	CB-15/20 A	42	unit
20	Convenience Outlet		
20.1	Convenience Outlet (3 gang)	144	unit
	Convenience Outlet (1 gang)	59	unit
21	Lighting Switch		
22	Switch (3 gang)	30	pcs
	Switch (2 gang)	8	pcs
23	Accessories		<b>1</b>
23.1	Junction Box (2x3 inc)	65	pcs
	Flexible electrical hose		
24	Electrical conduit (PVC)		
24.1	PVC 1-1/2 inc	65	length
24.2	PVC 3/4 inc	80	length
25	PVC 1/2 inc	190	length
26	Electrical Tape	45	pcs
27	Tie wire	5	kl
	Electrical Panel Board	12	pcs
	w/ enclosure & accessories		•
30	Emergency light set w/ complete accessories	59	unit
В	Equipment Rental @ 8 hrs/day		
C	Labor		
	Installation labor	1.00	LOT
	Test & commissioning	1.00	LOT
Π	Estimated Direct Cost(EDC)=A+B+C		
	Indirect Cost/Mark-Up		
	Overhead, Contingencies & Miscelaneous @ 12% of EDC	<u> </u>	
	Profit @ 8% of EDC	<u> </u>	
	Sub-Total		
с	5% Value Added Tax of D + E		
	Total Cost = $D + E + F$		
	Unit Cost		
н			
VIII	MECHANICAL WORKS		
	Materials		
1	Transformer		

	Window Type, 2hP	1.0	unit
	Window Type, 1.5 TR	1.0	unit
1.1			
1.2	Window Type, 2 HP	2.0	units
1.3	Split Type, Floor Mounted, 3TR w/ complete accessories	1.0	units
	Window Type, 2 HP	1.0	unit
2	Split Type, Ceiling Mounted, 5TR w/ complete accessories	1.0	unit
2.1	Split Type, Floor Mounted, 3TR w/ complete accessories	1.0	unit
	Window Type, 2 HP	1.0	unit
3	Split Type, Floor Mounted, 3TR w/ complete accessories	2.0	units
4	Window Type, 2HP	2.0	units
5	Split Type, Ceiling Mounted, 1TR w/ complete accessories	1.0	unit
6	Split Type, Ceiling Mounted, 1TR w/ complete accessories	1.0	unit
7	Window Type, 1TR	1.0	unit
8	Window Type, 2 HP	1.0	unit
9	Split Type, Ceiling Mounted, 1.5 TR w/ complete accessories	1.0	unit
10	Window Type, 2HP	3.0	units
	Split Type, Floor Mounted, 3TR w/ complete accessories	2.0	units
	Window Type, 2HP	1.0	unit
	Window Type, 2HP	1.0	unit
	Split Type, Ceiling Mounted, 3TR w/ complete accessories	1.0	units
	Split Type, Ceiling Mounted, 1.5 TR w/ complete accessories	1.0	unit
	Window Type, 2HP	2.0	units
	Window Type, 1.5 TR	1.0	unit
	Split Type, Ceiling Mounted, 1 TR w/ complete accessories	1.0	unit
	Split Type, Ceiling Mounted, 3TR w/ complete accessories	1.0	unit
	Split Type, Floor Mounted, 3TR w/ complete accessories	1.0	unit
B	Equipment Rental @ 8 hrs/day		
	Masonry Drill	1.00	LOT
	Demolition Hammer	1.00	LOT
	Labor		
L L		20.00	dave
	Leadman/Foreman	29.00	days
	Skilled Worker/Aircon Installer	58.00	days
	Laborer/Helper (DOLE's minimum wage for region 7)	58.00	days
	Estimated Direct Cost(EDC)=A+B+C		
	Indirect Cost/Mark-Up		

	Overhead, Contingencies & Miscelaneous @ 12% of EDC		
Profit @ 8% of EDC			
	Sub-Total		
F	5% Value Added Tax of D + E		
G	Total Cost = D + E + F		
Н	Unit Cost		
PROJECT	: PROPOSED CONSTRUCTION/IMPROVEMENT OF MEZ TEN	/IPORARY C	<b>FFICE AT AA</b>
LOCATION	: MACTAN ECONOMIC ZONE, LAPU-LAPU CITY		
Date	: JANUARY 2020		

## SUMMARY:

ITEM #	DESCRIPTION	UNIT
Ι.	GENERAL REQUIREMENTS	LOT
11.	EXCAVATION WORKS	CU.M
<i>III.</i>	CONCRETE WORKS	CU.M
	STEEL WORKS (COLUMN, BEAMS, MEZZANINE FLOOR AND FLOOR	
IV.	FRAMING	SQ.M
V.	FLOOR, WALL AND CEILING FINISHES	LOT
VI.	DOORS, WINDOWS AND PLUMBING WORKS	LOT
VII	ELECTRICAL WORKS	LOT
VIII	MECHANICAL WORKS	LOT
	ESTIMATED TOTAL PROJECT COST (PHp) =	

Prepared :

## LOUIE EVANS E. ESOTO

Division Chief II, EMD

Checked and Verified:

ISAGANI B. PULVERA

Department Manager, Operations

UNIT COST	TOTAL COST	REMARKS
		-
		1
		<u> </u>

Image: style s	r	
Image: style s		
Image: style s		
Image: style s		
Image: style s		
Image: state of the state of		
Image: state of the state of		
Image: style s		
Image: state of the state of		
Image: style s		
Image: set of the		
Image: state intermediate in		
Image: state s		
Image: state s		
Image: state of the state of		
Image: state s		
Image: state s		
Image: style s		
Image: state of the state of	ļ	
Image: style s		
Image: set of the		
Image: Section of the section of th		
Image: Section of the section of th		
Image: Constraint of the second se		
Image: Constraint of the second se	ļ	
Image: Section of the section of th		
Image: Constraint of the second se		
Image: Constraint of the second se		
Image: Sector of the sector		
Image: Constraint of the second se		
Image: Constraint of the second se		
Image: Constraint of the second se		
	ļ	

	]
	Ground floor is not included
	Ground noor is not included
	Use existing celing at ASD
	and EHSD

r		
	1	
	•	
	I	BY PEZA/MECO
		By PEZA/MECO
		By PEZA/MECO
		By PEZA/MECO

	By PEZA/MECO
	By PEZA/MECO
	, ,
	Supplied by PEZA
	Lico Evicting Emorgonau
	Use Existing Emergency
	Use Existing Emergency Lights

	Existing, Relocated, MIS OFFICE
	Existing, Relocated, MIS
	Server area
	Existing, Relocated, EMD
	New, EMD
	Existing, Relocated, EAD
	Existing, Relocated, EAD
	Existing, Relocated, EAD
	Existing, Relocated, FSD
	Existing, Relocated, FSD
	Existing, Relocated, COA
	New- DM SuSD
	New- DM Operations
	Existing, Relocated,
	Lactating Room
	Existing, Relocated, Meeting
	Room
	New, Cashier
	Existing, Relocated, EHSD
	Existing, Relocated, DG,s
	Office
	Existing, Relocated, DZA's
	Office
	Existing, Relocated, OZA
	New, OZA
	Existing, Relocated, BAC
	Office
	Existing, Relocated, ASD
	Existing, Relocated, ASD
	New, ASD
	Existing, Relocated,
	Conference Room
	Existing, Relocated,
	Conference Room
ļ	
<u> </u>	
	l

**I BUILDING** 

QUANTITY	AMOUNT	REMARKS
1.00		
82.30		
22.67		
288.00		
1.00		
1.00		
1.00		
1.00		
	-	

Recommending Approval:

RUFINO RANULFO Z. SAN JUAN IV OIC- DZA

Approved:

Bgen. CHARITO B. PLAZA, MNSA PhD.

Director General and Zone Administrator for MEZ and VisMin SEZ's