

RFQ No.	2019-11-0069
Date	29 November 2019

**REQUEST FOR QUOTATION**  
(Alternative Mode – Small Value Procurement)

Name of Company:

---

Address:

---

The Philippine Economic Zone Authority (PEZA), through its Bids and Awards Committee (BAC) will undertake **Alternative Mode – Small Value Procurement** in accordance with Sec. 53.9 of the 2016 Revised Implementing Rules and Regulations of the Republic Act No. 9184.

Name of Project	<b>Repair and Repainting of Road Centerlines, Pedestrian Lanes, Gutter Curbs and Road Humps</b>
Technical Specifications/Description	Attached Annex "A"
Approved Budget for the Contract (ABC)	<b>PhP223,590.00</b>
Deadline of Submission of Quotation	<b>05 December 2019</b>

Interested appraisers may submit their duly accomplished Price Quotation Form (Annex A) on or before the deadline of submission of bids to the BAC Secretariat at the PEZA Head Office, 5Floor, PNOC Bldg.5, DOE-PNOC Complex, Energy Center, Rizal Drive, BGC, Taguig City.

Bidders must submit sealed quotation/s in the address given above together with the following documentary requirements:

- 1) PhilGEPS Registration Number;
- 2) Valid and Current Mayor's/Business Permit 2019;
- 3) Omnibus Sworn Statement (OSS);

Award of contract shall be given to the lowest calculated bidder which complies with the technical specifications (Annex A) and General Terms and Conditions (Annex B).

For any clarification, you may contact/email BAC Secretariat at telephone nos. (02) 5513451 local 200 or 5513429.

  
**TERESO O. PANGA**  
BAC, Chair

B

Annex "A"

**SCOPE OF WORK**

**Name of Project** : Repair and Repainting of Road Centerlines, Pedestrian Lanes, Gutter Curbs and Road Humps  
**Location** : Pampanga Economic Zone, Pulung Cacutud, Angeles City Pampanga

**A. GENERAL REQUIREMENTS**

**1. SCOPE**

Furnish all materials, labor, equipment, testing and all other facilities for the satisfactory performance of all work necessary for the completion of the project.

**2. MOBILIZATION / DEMOBILIZATION**

Mobilization shall include transportation to the site of contractor's plant, materials, equipment, employees and furnishings and temporary facilities. Demobilization shall include dismantlement and removal from the site of contractor's plant, materials and equipment and all temporary facilities. Demobilization includes clean-up of the site after completion of the contract work.

**3. CONSTRUCTION SAFETY AND HEALTH**

The contractor shall provide appropriate personal protective equipment, the required PPE for all workers shall be safety shoes, working gloves and vest. Proper procedures for working at heights should be followed.

**B. REPAIR AND REPAINTING OF ROAD CENTERLINES, PEDESTRIAN LANES, GUTTER CURBS AND ROAD HUMPS**


Work shall cover the following items:

1. Repair of curbs approx. 78.24 meters
2. Repainting of curbs (Reflectorized traffic paint, black and yellow) (B/S) 260.80 sq. m.
3. Repainting 4 Road humps (Reflectorized traffic paint, black and yellow)
4. Repainting 5 Pedestrian Lanes (Reflectorized traffic paint, white)
5. Repainting of centerline 326 m (Reflectorized traffic paint, white)

**C. DURATION OF PROJECT**

Commencement of projects shall be 30 calendar days from receipt of Notice to Proceed/Work Order/Purchase Order whichever is applicable.

Approved by:



**Engr. April Joy R. Medico**

Zone Manager, Pampanga Economic Zone

Annex "B"  
**PRICE QUOTATION FORM**  
 (Financial Bid)s

**DDG TERESO O. PANGA**

Chairperson, Bids and Awards Committee  
 Philippine Economic Zone Authority (PEZA)  
 5Floor, PNOB Bldg.5, DOE-PNOB Complex, Energy Center  
 Rizal Drive, BGC, Taguig City

Thru: BAC Secretariat

Dear Sir:

After having carefully read and accepted the Terms and Conditions of this RFQ and followed Instructions to Bidders, hereunder is our quotation/s for the items as follows:

No	DESCRIPTION	QTY.	UNIT	UNIT COST	AMOUNT
A.	Materials				
	Epoxy Primer White (B/S)	36.00	gals	_____	_____
	Reflectorized traffic paint, black (B/S)	7.00	gals	_____	_____
	Reflectorized traffic paint, yellow (B/S)	40.00	gals	_____	_____
	Reflectorized traffic paint, white (B/S)	16.00	gals	_____	_____
	Lacquer thinner	4.00	gals	_____	_____
	Paint brush 4"	6.00	pcs	_____	_____
	Baby roller	6.00	pcs	_____	_____
	Road Warning Signage / Road Barriers	1.00	lot	_____	_____
	Cement	16.00	bags	_____	_____
	Sand	1.00	cu.m	_____	_____
	Trowel	2.00	pcs	_____	_____
	Working Gloves (Free Size)	5.00	pcs	_____	_____
	Face Mask	6.00	pcs	_____	_____
	High Visibility Clothing w/ reflective stripes	6.00	pcs	_____	_____
B.	Mobilization / Demobilization	1.00	lot	_____	_____

*R*



<b>C. Labor</b>					
1 - Foreman	13.50	m-day	_____	_____	
2 - Skilled Workers	3.50	m-day	_____	_____	
2 - Helpers / Laborers	13.50	m-day	_____	_____	
1 - Safety Officer	13.50	m-day	_____	_____	
		<b>Sub-Total</b>		_____	
<b>D. Estimated Direct Cost (EDC) = A + B + C</b>					
<b>E. Indirect Cost / Mark-up Overhead, Contingencies &amp; Miscellaneous (15% of EDC)</b>					
<b>Profit (10% of EDC)</b>					
				<b>Sub-Total</b>	_____
<b>F. VAT (5% of EDC+OCM+Profit)</b>					
<b>G. Total Cost = D + E + F</b>					
<b>TOTAL ESTIMATED DIRECT COST</b>					
<b>TOTAL INDIRECT COST / MARK-UP</b>					
<b>TOTAL VALUE ADDED TAX</b>					
<b>TOTAL PROJECT COST</b>					

\_\_\_\_\_  
Signature over Printed Name

\_\_\_\_\_  
Office Telephone No. / Mobile Telephone No.

\_\_\_\_\_  
Email address/es

**INSTRUCTIONS:**

(1) Accomplish this RFQ correctly and accurately.  
(2) Do not alter the contents of this form in any way.  
(3) Failure to comply with any of the mandatory requirements will disqualify your quotation.  
(4) Failure to follow these instructions will disqualify your entire quotation.

*R,*